### **Schedule of Accreditation**

issued by

### **United Kingdom Accreditation Service**

2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK



2545

Accredited to ISO/IEC 17025:2017

#### **MATtest Site Services Limited**

Issue No: 023 Issue date: 06 March 2024

10 Queenslie Point Contact: Mr M Osbaldstone Queenslie Industrial Estate

Queenslie Industrial Estate
Tel: +44 (0)141 774 4032
120 Stepps Road
Fax: +44 (0)141 774 3552
Glasgow
E-Mail: info@mattest.site

G33 3NQ Website: www.mattest.site

#### Testing performed by the Organisation at the locations specified below

#### Locations covered by the Organisation and their relevant activities

#### **Laboratory locations:**

Location details		Activity	Location code
Address 10 Queenslie Point Queenslie Industrial Estate 120 Stepps Road Glasgow G33 3NQ	Contact: Mr M. Osbaldstone  Tel: +44 (0)141 774 4032  Mob: +44 (0) 7739 363 554  Email: info@mattest.site.org	Administration, concrete and soils	А
Address 42a Seafield Road Inverness IV1 1SG	Contact: Mr M. Osbaldstone  Tel: +44 (0)141 774 4032  Mob: +44 (0) 7739 363 554  Email: info@mattest.site.org	Aggregates, concrete and soils	В

#### Site activities performed away from the locations listed above:

Location details		Activity	Location code
All locations suitable for the activities listed	Contact: Mr M. Osbaldstone  Tel: +44 (0)141 774 4032  Mob: +44 (0) 7739 363 554  Email: info@mattest.site.org	Site sampling and testing	X

Assessment Manager: AW3 Page 1 of 4



#### 2545 Accredited to ISO/IEC 17025:2017

### Schedule of Accreditation issued by

# United Kingdom Accreditation Service 2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK

#### **MATtest Site Services Ltd**

Issue No: 023 Issue date: 06 March 2024

Testing performed by the Organisation at the locations specified

#### **DETAIL OF ACCREDITATION**

	T	T	1
Materials/Products tested	Type of test/Properties measured/Range of measurement	Standard specifications/ Equipment/Techniques used	Location Code
AGGREGATES	Sampling coarse, fine and all- in aggregates - from flattened stockpiles	BS EN 932-1:1997	Х
	Sample reduction	BS EN 932-2:1999	X
	Water content	BS EN 1097-5:2008	В
BITUMINOUS MIXTURES	Measurements of temperature	BS EN 12697-13:2017	X
for roads and other paved areas	Sampling -from the material around the augers of the paver -workable heaps	BS EN 12697-27:2017	х
	Sampling of finished material - core cutting method	BS EN 12697-27:2017	X
	Sampling coated chippings from stockpiles	BS EN 12697-27:2017	Х
	Preparation of samples for the determination of binder content, water content and grading	BS EN 12697-28:2020	Х
	Rate of spread of binder - carpet tile method	BS EN 12272-1:2002	Х
BITUMINOUS ROAD SURFACING	In-situ density - dielectric method	Documented In-House Method No TOP 5	Х
	In-situ density - nuclear method	Documented In-House Method No TOP 10	Х
CONCRETE - fresh	Sampling - spot - composite	BS EN 12350-1:2019	х
	Slump	BS EN 12350-2:2019	X
	Air content – pressure method	BS EN 12350-7:2019	X
	Making specimens for strength	BS EN 12390-2:2019	А

Assessment Manager: AW3 Page 2 of 4



#### 2545 Accredited to ISO/IEC 17025:2017

#### **Schedule of Accreditation** issued by

## United Kingdom Accreditation Service 2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK

#### **MATtest Site Services Ltd**

**Issue No:** 023 Issue date: 06 March 2024

#### Testing performed by the Organisation at the locations specified

Materials/Products tested	Type of test/Properties measured/Range of measurement	Standard specifications/ Equipment/Techniques used	Location Code
CONCRETE - hardened	Shape, dimensions	BS EN 12390-1:2021	В
	Curing	BS EN 12390-2:2019	В
	Compressive strength of cubes	BS EN 12390-3:2019	В
	Density	BS EN 12390-7:2019	В
GEOTECHNICAL INVESTIGATION and TESTING - Laboratory testing of soil	Water content	BS EN ISO 17892-1:2014 +A1:2022	АВ
ROAD PAVEMENT SURFACES	Pavement surface macrotexture depth using a volumetric patch technique	BS EN 13036-1:2010	X
	Surface regularity using a rolling straight-edge	TRRL Supplementary Report 290:1977	X
SOILS for civil engineering purposes	Waters content - oven drying method	BS 1377-2:2022	АВ
	MCV - natural moisture content	BS 1377-2:2022	А
	Dry density/moisture content relationship - 2.5 kg rammer - 4.5 kg rammer - vibrating hammer	BS 1377-2:2022	В
	In-situ density - sand replacement method - core cutter method	BS 1377-9:1990	X
	In-situ bulk density - nuclear method - compliance tests	BS 1377-9:1990	х

Assessment Manager: AW3 Page 3 of 4



#### 2545 Accredited to ISO/IEC 17025:2017

#### **Schedule of Accreditation** issued by

## United Kingdom Accreditation Service 2 Pine Trees, Chertsey Lane, Staines-upon-Thames, TW18 3HR, UK

#### **MATtest Site Services Ltd**

**Issue No:** 023 Issue date: 06 March 2024

#### Testing performed by the Organisation at the locations specified

Materials/Products tested	Type of test/Properties measured/Range of measurement	Standard specifications/ Equipment/Techniques used	Location Code
SOILS for civil engineering purposes (cont'd)	In-situ California Bearing Ratio (CBR)	BS 1377-9:1990	Х
	Moisture condition value	Scottish Development Department Technical Memorandum SH7/83	X A
	MCV - natural moisture content	BS 1377-4:1990	Х
	Sampling soils - from undisturbed material - from disturbed material	Documented In-House Method No TOP 1:2018	X
	Dynamic cone penetrometer	Documented In-House Method No TOP 9:2009	Х
	Vertical deformation and strength characteristics of soil by the plate loading test	BS 1377-9:1990	Х
	Equivalent CBR using the plate load test	DMRB: Volume 7: Pavement design and Maintenance - Foundation HD 25/94 & IAN 73/06	X
	END	,	

Assessment Manager: AW3 Page 4 of 4